

A N T E M A S U R A T O A R E

Deviz DEMO08 DEMOLARE NISE LABORATOR

=====

Nr.	Simbol articol	UM	CANTITATEA
	crt.		

=====

001	CL17B1	[1]TONA	4.200
DEMONTAREA CONSTRUCTIILOR METALICE FARA			
RECUPERAREA SUBANSAMBLELOR REFOLOSIBILE			

002	TRB05A25	TONA	4.200
TRANSPORTUL MATERIALELOR PRIN PURTAT			
DIRECT.MATERIALE INCOMODE SUB 25 KG			
DISTANTA 50M			

003	TRI1AA01F1	TONA	4.200
INCARCAREA MATERIALELOR,GRUPA A-GRELE SI			
MARUNTE,PRIN TRAN.PINA LA 10M RAMPA SAU			
TEREN-AUTO CATE			

004	TRA02A05	TONA	4.200
TRANSPORTUL RUTIER AL MATERIALELOR,			
SEMIFABRICATELOR CU AUTOCAMIONUL PE			
DIST.= 5 KM.			

005	TRI1AA08F1	TONA	4.200
DESCARCAREA MATERIALELOR,GRUPA A-GRELE			
SI MARUNTE PRIN TRANS.PINA LA 10M AUTO-			
RAMPA,TEREN CATEG.			

006	CL17B1	[1]TONA	0.200
DEMONTAREA CONSTRUCTIILOR METALICE FARA			
RECUPERAREA SUBANSAMBLELOR REFOLOSIBILE			

007	RPCT03B1	M.C.	7.200
DEMOLAREA ZIDURILOR DIN CARAMIDA CU			
MORTAR VAR+CIMENT VOLUM PESTE 1,000 MC *			

008	RPCT09B1	M.C.	1.600
DEMOLAREA ELEMENTELOR DE BETON SIMPLU SI			
ARMAT CU MIJLOACE MANUALE CU DOZAJ PESTE			
150 KG CIM.LA			

009	CO01A1	MP.	6.000
TROTUAR DIN BETON SIMPLU TURNAT PE LOC			

009	2100957	M.C.	0.486
BETON DE CIMENT B 200 STAS 3622			

010	TRA06A10	TONA	1.200
TRANSPORTUL RUTIER AL BETONULUI-			
MORTARULUI CU AUTOBETONIERA DE 5,5MC			
DIST. =10KM			

011	TRB05A25	TONA	16.000
TRANSPORTUL MATERIALELOR PRIN PURTAT			
DIRECT.MATERIALE INCOMODE SUB 25 KG			
DISTANTA 50M			

012 TRI1AA01F1 TONA 16.000
INCARCAREA MATERIALELOR, GRUPA A-GRELE SI
MARUNTE, PRIN TRAN.PINA LA 10M RAMPA SAU
TEREN-AUTO CATE

013 TRA01A05P TONA 16.000
TRANSPORTUL RUTIER AL PAMINTULUI SAU
MOLOZULUI CU AUTOBASCULANTA DIST.= 5 KM

014 TRI1AA08F1 TONA 16.000
DESCARCAREA MATERIALELOR, GRUPA A-GRELE
SI MARUNTE PRIN TRANS.PINA LA 10M AUTO-
RAMPA, TEREN CATEG.

Intocmit,

Verificat,



25.06.2020