

ANTEMASURATOARE

INSTALATIA : COCSARE

LUCRAREA: DEMOLARE COLOANA 02-C4 SI REFIERBATOR 02-S9

COD DEZV DEM02C4

A. MANOPERA NORMATIV (UTILAJE STATICE SI CONDUCTE)

NR. CRT	DENUMIREA LUCRARII	UM	CANT	SIMBOL NORMATIV/ UM	ORE NORMATE	TOTAL
1	Demontat legaturi conducte DN350 prin taiere mecanica	to	2.86		36.98	
2	Demontat legaturi conducte DN300 prin taiere mecanica	to	2.75		36.98	
3	Demontat legaturi conducte DN200 prin taiere mecanica	to	1.60		36.98	
4	Demontat legaturi conducte DN150 prin taiere mecanica	to	0.60		36.98	
5	Demontat legaturi conducte DN50-150 prin taiere mecanica	to	1.20		42.80	
6	Demontat coloana de pe pozitie (6600x1100 si 9000x2000mm)	buc	1.00		72.45	
7	Demontat legaturi conducte 02-S9 teava DN50-200	to	1.75		41.21	
8	Debitare cu flacara oxiacetilenica coloana, conducte si schimbator	to	51.00		2.57	
	TOTAL ORE NORMATE	ORE				
	TARIF SERVICE	LEI / ORA				
	TOTAL VALOARE ORE NORMATE	LEI				

B. MANOPERA NORMATIV (SCHELE)

NR. CRT	DENUMIREA LUCRARII	UM	CANT	SIMBOL NORMATIV/ UM	ORE NORMATE	TOTAL
1	Montat si demontat schele	mc	200		0.55	
	TOTAL ORE NORMATE	ORE				
	TARIF SERVICE	LEI / ORA				
	TOTAL VALOARE ORE NORMATE	LEI				

C. MANOPERA NORMATIV (IZOLATII TERMICE)

NR. CRT	DENUMIREA LUCRARII	UM	CANT	SIMBOL NORMATIV/ UM	ORE NORMATE	TOTAL
	TOTAL ORE NORMATE	ORE				
	TARIF SERVICE	LEI / ORA				
	TOTAL VALOARE ORE NORMATE	LEI				

D. UTILAJE

NR. CRT	DENUMIRE UTILAJ	NR. ORE	TARIF ORAR	TOTAL
1	Macara 250tf	24.00		
2	Macara 80tf	32.00		
3	Trailer 45t	20.00		
	TOTAL UTILAJE	LEI		

E. DEMONTAJ (Conform licitatie demolari 2020)

NR. CRT	DENUMIREA LUCRARII	UM	CANT	TARIF ORAR	TOTAL
	TOTAL DEMONTAJ	LEI			

TOTAL GENERAL A+B+C+D+E	LEI fara TVA	
-------------------------	--------------	--

ROTEL-LUKOIL S.A.
BIROU C.P.S.C.T.
SEF BIROU
CIOBANU ALEXANDRU

06.02.2020.