

NORMATIV INLOCUIRE CUPLAJ

A.	DENUMIRE LUCRARE	ORE
Nr.		
1	Pregatirea lucrarii	0.78
2	Demontat conducte sistem ungere	12.00
3	Demontat carcasa superioara cuplaj	6.50
4	Demontat carcasa inferioara cuplaj	6.50
5	Demontat mosor turbina-compresor	8.80
6	Demontat inel manson semicupla compresor	3.25
7	Demontat inel manson semicupla turbina	3.25
8	Demontat manson semicupla compresor	3.60
9	Demontat manson semicupla turbina	3.60
10	Extras semicupla (butuc) compresor de pe arbore	16.00
11	Extras semicupla (butuc) turbina de pe arbore	16.00
12	Demontat capace lagare radiale si radial-axial	10.00
13	Demontat carcasa sustinere lagar radial-axial	9.80
14	Demontat lagare radiale	12.00
15	Demontat lagar axial	8.40
16	Demontat piulita strangere disc axial	1.00
17	Extras disc axial de pe arbore	3.00
18	Curatat piese demontate	8.00
19	Verificat / efectuat jocuri radiale	12.00
20	Verificat / efectuat joc axial lagar	14.00
21	Curatat arbore compresor zona semicupla	2.00
22	Curatat arbore turbina zona semicupla	2.00
23	Verificat si masurat arbore compresor zona semicupla	4.80
24	Verificat si masurat arbore turbina zona semicupla	4.80
25	Verificat si masurat cuplaj nou	6.00
26	Montat disc axial pe arbore	3.20
27	Montat piulita strangere disc axial	1.00
28	Montat lagar axial	6.00
29	Montat lagare radiale	10.00
30	Montat carcasa sustinere lagar radial-axial	8.00
31	Montat capace lagare radiale si radial-axial	10.00
32	Montat conducte sistem ungere lagare	16.80
33	Tusat si montat semicupla compresor pe arbore	28.00
34	Tusat si montat semicupla turbina pe arbore	28.00
35	Anulat sistem ungere cuplaj vechi	16.00
36	Verificari si ajustari	18.00
37	Efectuat prealinieri compresor-turbina	16.00
38	Montat inel manson semicupla compresor	3.35
39	Montat inel manson semicupla turbina	3.35
40	Montat manson semicupla compresor	3.75
41	Montat manson semicupla turbina	3.75
42	Montat mosor turbina-compresor	8.90
43	Aliniat compresor-turbina	42.00
44	Montat carcasa inferioara cuplaj	6.65
45	Montat carcasa superioara cuplaj	6.65
46	Punere in functiune cu asistenta tehnica	24.00
	Operatii executate turbina P=1570 kW	
1	Demontat capota protectie turbina	18.00

2	Demontat carcasa protectie lagar radial cap cuplaj	5.00
3	Demontat capac lagar radial cap cuplaj	4.60
4	Demontat lagar radial cap cuplaj	7.50
5	Curatat piese demontate	4.50
6	Verificat / efectuat joc lagar radial cap cuplaj	16.00
7	Montat lagar radial cap cuplaj	7.60
8	Montat capac lagar radial cap cuplaj	4.60
9	Montat carcasa protectie lagar radial cap cuplaj	5.00
10	Montat capota protectie turbina	21.00
TOTAL ORE		535.28

Sef Serviciu Devize - Contracte
C. Alupoaipei



Specialist principal Devize
A. Ciobanu

 25.11.2018