

CENTRALIZATOR

MONTAJ STUTURI PRELEVARE PROBE SI DRENAJ - INSTALATIA RC

Nr. crt.	Rev.	Cod deviz	Devize pe categorii de lucrari	Total	Observatii
				lei	
o1	o2	o3	o4	o5	o6
1	0	SPP008	MONTAJ STUTURI PRELEVARE PROBE SI DRENAJ 16 BUC - INSTALATIA RC		
TOTAL GENERAL - LEI					
CHELTUIELI NEPREVAZUTE 5%					
CHELTUIELI PROIECTARE					
CHELTUIELI AUTORIZARE ISCIR					
TOTAL GENERAL - LEI - (fara TVA)					



S.C. LUKOIL S.A.
 C.P.S.C.T.
 IORDAN
 ALEXANDRU

ANTENASURATOARE

Deviz SPP008 Stuturi prelevare probe si
drenaj

Nr.	Simbol articol	UM	CANTITATEA
	crt.		

001	CB47A1	MP.	200.000
MONTAREA SI DEMONTARE SCHELEI MET			
TUBULARE PT LUCRARI PE SUPRAFETE			
VERTICALE H<30,0M			

002	MIM09C1	PER	3.000
DEMONT.FLANSELOR (ROTUNDA, PLATA, GIT)			
SUDATE PE CONDUCTA LA 1M ADINC.			
SUPRATERAN PINA LA H=3M DR=50			

003	MIM09E1	PER	3.000
DEMONT.FLANSELOR (ROTUNDA, PLATA, GIT)			
SUDATE PE CONDUCTA LA 1M ADINC.			
SUPRATERAN PINA LA H=3M DR=80			

004	MIM09H1	PER	17.000
DEMONT.FLANSELOR (ROTUNDA, PLATA, GIT)			
SUDATE PE CONDUCTA LA 1M ADINC.			
SUPRATERAN PINA LA H=3M DR=150			

005	MIM09I1	PER	4.000
DEMONT.FLANSELOR (ROTUNDA, PLATA, GIT)			
SUDATE PE CONDUCTA LA 1M ADINC.			
SUPRATERAN PINA LA H=3M DR=200			

006	MIM09J1	PER	3.000
DEMONT.FLANSELOR (ROTUNDA, PLATA, GIT)			
SUDATE PE CONDUCTA LA 1M ADINC.			
SUPRATERAN PINA LA H=3M DR=250			

007	MIM09K1	PER	5.000
DEMONT.FLANSELOR (ROTUNDA, PLATA, GIT)			
SUDATE PE CONDUCTA LA 1M ADINC.			
SUPRATERAN PINA LA H=3M DR=300			

008	TFB07B1	[1]BUC.	3.000
MONTAT BLINDE DN.50 MM			

009	TFB07D1	[1]BUC.	3.000
MONTAT BLINDE DN.80 MM			

010	TFB07G1	[1]BUC.	17.000
MONTAT BLINDE DN.150 MM			

011	TFB07H1	[1]BUC.	4.000
MONTAT BLINDE DN.200 MM			

012	TFB07I1	[1]BUC.	3.000
MONTAT BLINDE DN.250 MM			

013	TFB07J1	[1]BUC.	5.000
MONTAT BLINDE DN.300 MM			

014	MIJ43A1	[1]BUC.	64.000
EXECUTAT SUDURI LA COND, FITINGURI SI			
FLANSE DIN OTEL CARBON PANA LA DN 25MM			
(INCLUSIV)			

015	MIL71A1	[1]BUC.	64.000
PREINCALZIREA COND, IN ZONA CE URMEAZA A			
SE EXEC.SUDURA COND.AVIND DN PINA LA 80			
MM			

016	MIJ23A1	[1]BUC.	64.000
TRATAMENT TERMIC AL SUDURILOR LA			
CONDUCTE DIN OTEL ALIAT CONDUCTE.< 80 MM			

017	MIL62A1	[1]BUC.	64.000
CONTROLUL CU LICHID PENETRANT A SUD DE			
COLT LA CONDUCTE CF.CAIET SARCINI DN			
COND PINA LA 160MM			

018	MIJ21A1	[1]M	39.000
PROBA HIDRAULICA A CONDUCTELOR LA			
PRESIUNE DE PINA LA 100 ATM. < 80 MM			

019	MIJ21B1	[1]M	90.000
PROBA HIDRAULICA A CONDUCTELOR LA			
PRESIUNE DE PINA LA 100 ATM. 80-150.MM.			

020 MLJ21C1 [1]M 110.000
PROBA HIDRAULICA A CONDUCTELOR LA
PRESIUNE DE PINA LA 100 ATM. 150-400.MM.

021 YC01RON LEI.
DIFERENTA PRET MATERIALE - RON

022 MLJ39A1 [1]BUC. 3.000
MONTAREA GARNITURILOR LA IMB IN FLANSE
DUPA EFECT PROBELOR IN INST TEHN PN<25AT
T<225C DN<50MM

221 MLJ39B1 [1]BUC. 20.000
MONTAREA GARNITURILOR LA IMB IN FLANSE
DUPA EFECT PROBELOR IN INST TEHN PN<25AT
T<225C DN=65-150

023 MLJ39C1 BUC. 7.000
MONTAREA GARNITURILOR LA IMB IN FLANSE
DUPA EFECT PROBELOR IN INST TEHN PN<25AT
T<225C DN=200-25

024 MLJ39D1 [1]BUC. 5.000
MONTAREA GARNITURILOR LA IMB IN FLANSE
DUPA EFECT PROBELOR IN INST TEHN PN<25AT
T<225C DN=300-40

025 AUT6729 ORA 8.000
MACARA PE PNEURI 10-14,9TF

026 AUT5615 ORA 8.000
TRAILER 20T

Intocmit,

Verificat,

SISTEM INFORMATIC PROIECTAT DE FIRMA I N F S E R V (Tel:2109807)

BCI
gh
28.02.2017

S.C. PETROTEL-LUKOIL S.A.
BIROU C.P.S.C.T.
SEF BIROU
CIOBANU ALEXANDRU

28.02.2017

TABEL DE CALCUL
MONTAJ STUTURI PRELEVARE PROBE SI DRENAJ

Nr. crt.	Denumire	UM	Cantitate
1	RSMS DN 15-800#	buc	16.00
2	GS/IE DN 50 PN 25	buc	3.00
3	GS/IE DN 80 PN 25	buc	3.00
4	GS/IE DN 150 PN 25	buc	17.00
5	GS/IE DN 200 PN 25	buc	4.00
6	GS/IE DN 250 PN 25	buc	3.00
7	GS/IE DN 300 PN 25	buc	5.00
8	BLINDE Dn 50 PN 25	buc	3.00
9	BLINDE DN 80 PN 25	buc	3.00
10	BLINDE DN 150 PN 25	buc	17.00
11	BLINDE DN 200 PN 25	buc	4.00
12	BLINDE DN 250 PN 25	buc	3.00
13	BLINDE DN 300 PN 25	buc	5.00
14	MSS1 DN 150/DN15	buc	16.00
15	Niplu N1	buc	16.00
15	Niplu N3	buc	16.00
17	KMF DN 15	buc	16.00
TOTAL PROCURARE MATERIALE-RON FARA TVA			

S.C. PETROTEL-LUKOIL S.A.
BIROU C.P.S.C.T.
SEF BIROU
CIOBANU ALEXANDRU