

CENTRALIZATOR
IMPLEMENTARE APC LA INSTALATIA RC - DEMONTAT/MONTAT VENTILE

Nr. crt.	Rev.	Cod deviz	Devize pe categorii de lucrari	Total	Observatii
				lei	
o1	o2	o3	o4	o5	o6
1	0	VENT08	DEMONTAT/MONTAT VENTILE REGULATOARE - IMPLEMENTARE APC LA RC		
TOTAL GENERAL - LEI (fara TVA)					

S.C. PETROTEL-LUKOIL S.A.
 BIROU C.P.S.C.T.
 SEE BIROU
 CIOBANU ALEXANDRU

28. 11. 2016

A N T E M A S U R A T O A R E

Deviz VENT08 DEMONTAT/MONTAT VENTILE REGULATOARE IMPLEMENTARE APC LA RC

=====

Nr.	Simbol articol	UM	CANTITATEA
	crt.		

=====

001	M1M09A1	PER	20.000
DEMONT.FLANSELOR (ROTUNDA, PLATA, GIT)			
SUDATE PE CONDUCTA LA 1M ADINC.			
SUPRATERAN PINA LA H=3M DR=25			

002	TFB07A1	[1]BUC.	20.000
MONTAT BLINDE DN.40 MM			

003	M1M09B1	PER	20.000
DEMONT.FLANSELOR (ROTUNDA, PLATA, GIT)			
SUDATE PE CONDUCTA LA 1M ADINC.			
SUPRATERAN PINA LA H=3M DR=40			

004	TFB07A1	[1]BUC.	20.000
MONTAT BLINDE DN.40 MM			

005	M1M09C1	PER	32.000
DEMONT.FLANSELOR (ROTUNDA, PLATA, GIT)			
SUDATE PE CONDUCTA LA 1M ADINC.			
SUPRATERAN PINA LA H=3M DR=50			

006	TFB07B1	[1]BUC.	32.000
MONTAT BLINDE DN.50 MM			

007	M1M09E1	PER	24.000
DEMONT.FLANSELOR (ROTUNDA, PLATA, GIT)			
SUDATE PE CONDUCTA LA 1M ADINC.			
SUPRATERAN PINA LA H=3M DR=80			

008	TFB07D1	[1]BUC.	24.000
MONTAT BLINDE DN.80 MM			

009	M1M09F1	PER	16.000
DEMONT.FLANSELOR (ROTUNDA, PLATA, GIT)			
SUDATE PE CONDUCTA LA 1M ADINC.			
SUPRATERAN PINA LA H=3M DR=100			

010	TFB07E1	[1]BUC.	16.000
MONTAT BLINDE DN.100 MM			

011	M1M08A1	BUC.	10.000
DEMONT.ROBINET VENTIL, SERTAR, CLAPET.			
RETIN.OTEL (FONTA) <PN40, MONT.CANAL<1M			
ADINC (SUPRATER) H=3M DN=			

012	M1M08B1	BUC.	4.000
DEMONT.ROBINET.VENTIL, SERTAR, CLAPET.			
RETIN.OTEL (FONTA) <PN40, MONT.CANAL<1M			
ADINC (SUPRATER) H=3M DN=			

013	M1M08C1	BUC.	7.000
DEMONT.ROBINET VENTIL, SERTAR, CLAPET.			
RETIN.OTEL (FONTA) <PN40, MONT.CANAL<1M			
ADINC (SUPRATER) H=3M DN=			

014	M1M08E1	BUC.	6.000
DEMONT.ROBINET.VENTIL, SERTAR, CLAPET.			
RETIN.OTEL (FONTA) <PN40, MONT.CANAL<1M			
ADINC (SUPRATER) H=3M DN=			

015 M1M08F1 BUC. 4.000
DEMONT.ROBINET VENTIL,SERTAR,CLAPET.
RETIN.OTEL (FONTA)<PN40,MONT.CANAL<1M
ADINC (SUPRATER)H=3M DN=

016 M1J11A1 [1]TONA 3.800
DEM.COND.PIESE RACORDARE OTEL CARBON
PREFABR.ARMATURI ASAMBLARE SI SUPORTI
GATA CONF.< 80 MM (50

017 M1J11B1 [1]TONA 5.000
DEM.COND.PIESE RACORDARE OTEL CARBON
PREFABR.ARMATURI ASAMBLARE SI SUPORTI
GATA CONF.80-150.MM. (

018 M1L24A1 [6]M 10.700
POLIZAREA INTER.A CORDOANELOR DE SUDURA
LA UTILAJEIN VEDEREA EFECTUARII
CONTROLULUI NEDISTRUCTIV

019 M1L62A1 [1]BUC. 44.000
CONTROLUL CU LICHID PENETRANT A SUD DE
COLT LA CONDUCTE CF.CAIET SARCINI DN
COND PINA LA 160MM

020 M1L71A1 [1]BUC. 40.000
PREINCALZIREA COND,IN ZONA CE URMEAZA A
SE EXEC.SUDURA COND.AVIND DN PINA LA 80
MM

021 M1L71B1 [1]BUC. 4.000
PREINCALZIREA COND IN ZONA CE URMEAZA A
SE EXECUTASUDURA COND AVIND DN INTRE 80-
150 MM

022 M1J43A1 [1]BUC. 16.000
EXECUTAT SUDURI LA COND,FITINGURI SI
FLANSE DIN OTEL CARBON PANA LA DN 25MM
(INCLUSIV)

023 M1J43A1 [2]BUC. 14.000
EXECUTAT SUDURI LA COND,FITINGURI SI
FLANSE DIN OTEL CARBON CU DN INTRE 25 SI
50MM (INCLUSIV)

024 M1J43A1 [3]BUC. 10.000
EXECUTAT SUDURI LA COND,FITINGURI SI
FLANSE DIN OTEL CARBON CU DN INTRE 50 SI
80MM(INCLUSIV)

025 M1J43B1 [1]BUC. 4.000
EXECUTAT SUDURI LA CONDUCTE,FITINGURI SI
FLANSE DIN OTEL CARBON CU DN INTRE 80-
125MM

026 M1J23A1 [1]BUC. 20.000
TRATAMENT TERMIC AL SUDURILOR LA
CONDUCTE DIN OTEL ALIAT CONDUCTE.< 80 MM

027 M1J23B1 [1]BUC. 2.000
TRATAMENT TERMIC AL SUDURILOR LA
CONDUCTE DIN OTEL ALIAT CONDUCTE.80-150
MM.

028 M1L50A1 [1]BUC. 20.000
CONTROLUL CU RADIATII GAMA A SUD LA
COND.MONTATE LA H> 4M COND.DN PINA LA 50
MM GROS.PER.< 10 MM

029 M1L50C1 [1]BUC. 4.000
CONTROLUL CU RADIATII GAMA A SUD LA COND
MONT LA H>4M (TEHN.A) COND INTRE 102-
168MM GR.PER<10MM

030 M1J11A1 [2]TONA 3.800
MONTAT COND.PIESE RACORDARE OTEL CARBON
PREFABR.ARMATURI ASAMBLARE SI SUPORTI
GATA CONF.< 80 MM

031 M1J11B1 [2]TONA 5.000
MONTAT COND.PIESE RACORDARE OTEL CARBON
PREFABR.ARMATURI ASAMBLARE SI SUPORTI
GATA CONF.80-150.M

032 M1J11A1 [2]TONA 1.806
MONTAT COND.PIESE RACORDARE OTEL CARBON
PREFABR.ARMATURI ASAMBLARE SI SUPORTI
GATA CONF.< 80 MM

033 M1J11B1 [2]TONA 1.003
MONTAT COND.PIESE RACORDARE OTEL CARBON
PREFABR.ARMATURI ASAMBLARE SI SUPORTI
GATA CONF.80-150.M

034 CB47A1 MP. 155.000
MONTAREA SI DEMONTARE SCHELEI MET
TUBULARE PT LUCRARI PE SUPRAFETE
VERTICALE H<30,0M

035 M1J39A1 [1]BUC. 72.000
MONTAREA GARNITURILOR LA IMB IN FLANSE
DUPA EFECT PROBELOR IN INST TEHN PN<25AT
T<225C DN<50MM

036 M1J39B1 [1]BUC. 40.000
MONTAREA GARNITURILOR LA IMB IN FLANSE
DUPA EFECT PROBELOR IN INST TEHN PN<25AT
T<225C DN=65-150

037 IZA04A1 MP. 64.000
PREGATIREA SUPRAF.DE BETON SAU METAL
PRIN CURATIRE CU PERIA DE SIRMA

038 IZJ09A1 MP. 64.000
VOPS.INVELIT.DE TABLA LA COND. SI
APARATE,CU EMAIL ALUMINIU DOUA STRATURI
INCLUSIV GRUNDUIREA

040 TRI1AA01F1 TONA 2.810
INCARCAREA MATERIALELOR,GRUPA A-GRELE SI
MARUNTE,PRIN TRAN.PINA LA 10M RAMPA SAU
TEREN-AUTO CATE

041 TRI1AA08F1 TONA 2.810
DESCARCAREA MATERIALELOR,GRUPA A-GRELE
SI MARUNTE PRIN TRANS.PINA LA 10M AUTO-
RAMPA,TEREN CATEG.

042 TRB05A21 TONA 2.810
TRANSPORTUL MATERIALELOR PRIN PURTAT
DIRECT.MATERIALE INCOMODE SUB 25 KG
DISTANTA 10M

043 TRA02A03 TONA 2.810
TRANSPORTUL RUTIER AL MATERIALELOR,
SEMIFABRICATELOR CU AUTOCAMIONUL PE
DIST.= 3 KM.

044 AUT6738 ORA 32.000
MACARA PE PNEURI BRAT TELESCOPIC TELEMAT
HT125 12,5TF

045 YC01RON LEI.
DIFERENTA PRET MATERIALE - RON
PROCURARE MATERIALE CONFORM TABEL ANEXAT

Intocmit,

Verificat,

SISTEM INFORMATIC PROIECTAT DE FIRMA I N F S E R V (Tel:2109807)

S.C. PETROTEL LUKOIL S.A.
BIROU C.P.S.C.T.
SEE BIROU
CIOBANU ALEXANDRU

28. 11. 2016

BCG

gll

28.11.2016

CENTRALIZATOR MATERIALE -YC01 DEVIZ VENT08

Nr. crt.	Denumire material	UM	Cantitate	Pret unitar (RON)	Pret total (RON)
1	GS/IE DN25 PN40	buc.	12.00		
2	RE DN100/DN25	buc.	4.00		
3	FG DN25 PN40	buc.	2.00		
4	GS/IE DN 1"-300#	buc.	6.00		
5	GS/IE DN40 PN40	buc.	20.00		
6	RE DN80/DN40	buc.	6.00		
7	FG DN40 PN40	buc.	6.00		
8	FG DN 1"-600#	buc.	2.00		
9	GS/IE 1"-600#	buc.	2.00		
10	RE DN80/DN50	buc.	4.00		
11	FG DN50 PN40	buc.	2.00		
12	GS/IE DN50 PN40	buc.	32.00		
13	GS/IE DN2" -300#	buc.	4.00		
14	FG DN2" -600#	buc.	2.00		
15	GS/IE DN2" -600#	buc.	2.00		
16	GS/IE DN3" -600#	buc.	14.00		
17	GS/IE DN80 PN40	buc.	10.00		
18	GS/IE DN4" - 300#	buc.	16.00		
19	PREZON M12X80	buc.	32.00		
20	PREZON M16X100	buc.	64.00		
21	PREZON M20X110	buc.	16.00		
22	PIULITE M12	buc.	64.00		
23	PIULITE M16	buc.	128.00		
24	PIULITE M20	buc.	32.00		
TOTAL (RON) fara T.V.A.					