

CENTRALIZATOR VALORIC

**“Protectie anticoroziva estacada metalica sustinere conducte si
trasee cabluri- zona rampa descarcare produse grele CF”**

Nr. Crt.	DENUMIRE LUCRARE	COD DEVIZ	VALOARE FARA TVA (LEI)
o1	o2	o3	o4
1	Lucrari de vopsitorii constructii metalice estacada	VOPS98	
TOTAL (LEI) FARA TVA			
CHELTUIELI DIVERSE SI NEPREVAZUTE		15%	
TOTAL GENERAL (LEI) FARA TVA			

PETROTEL LUKOIL S.A.
BIROU C.P.S.C.T
SPECIALIST DEVIZE
DUMITRESCU CORNELIA

[Signature] 15.10.2019

A N T E M A S U R A T O A R E

Deviz VOPS98 VOPSITORII CONSTRUCTII METALICE ESTACADA

=====

Nr. Simbol articol crt.	UM	CANTITATEA
----------------------------	----	------------

=====

001 IZD02A1	TONA	90.000
CURATIRE RUGINA CU PERIE SIRMA A PIESELOR METALICE GRINZI ZABRELE, FERME, CONTRAVINTUIRI		

002 IZD03D1	TONA	90.000
VOPSIRE CU VOPS MINIU CU APARAT AER COMPR 1 STR PECONF SI CTII METAL EXEC DIN PROF GROS 8-12 MM		

003 IZD06B1	TONA	90.000
VOPSIRE 2 STRATURI CU VOPSEA ULEI LA CONSTRUCTII METALICE		

003 6106117	KG	-450.000
EMAIL ALB E.101-8 NTR 90-73		

003 6103218	KG	450.000
VOPSEA ULEI ORICE CULOARE		

004 CB47A1	MP.	1580.000
MONTAREA SI DEMONTARE SCHELEI MET TUBULARE PT LUCRARI PE SUPRAFETE VERTICALE H<30,0M		

005 TR11AA01F1	TONA	33.980
INCARCAREA MATERIALELOR, GRUPA A-GRELE SI MARUNTE, PRIN TRAN. PINA LA 10M RAMPA SAU TEREN-AUTO CATE		

006 TR11AA08F1	TONA	33.980
DESCARCAREA MATERIALELOR, GRUPA A-GRELE SI MARUNTE PRIN TRANS. PINA LA 10M AUTO- RAMPA, TEREN CATEG.		

007 TRB05A25	TONA	33.980
TRANSPORTUL MATERIALELOR PRIN PURTAT DIRECT. MATERIALE INCOMODE SUB 25 KG DISTANTA 50M		

008 TRA02A02	TONA	33.980
TRANSPORTUL RUTIER AL MATERIALELOR, SEMIFABRICATELOR CU AUTOCAMIONUL PE DIST.= 2 KM.		

Intocmit,

Verificat,

SISTEM INFORMATIC PROIECTAT DE FIRMA I N F S E R V (Tel:2109807)



15.10.2019

PETROTEL LUKOIL S.A.
BIROU C.P.S.C.T
SPECIALIST DEVIZE
DUMITRESCU CORNELIA

 15.10.2019