

ANTEMASURATOARE

LUCRARE: AMENAJARI INTERIOARE PAVILION A PLK - INCAPERI DE PRODUCTIE ADMINISTRATIVE ETAJ 1
PAVILION ADMINISTRATIV

A. MANOPERA NORMATIV

NR. CRT	DENUMIREA LUCRARII	CANT	UM	ORE NORMATE / UM	TOTAL
	FINISAJE				
1	Glet la pereti si tavane	290.90	mp		
2	Amorsa + zugraveli lavabile 2 straturi culoare alba	290.90	mp		
3	Montat coltare AL la pereti si grinzi	152.00	m		
4	Demontat tavan fals casetat	85.00	mp		
5	Montat tavan fals casetat	85.00	mp		
6	Desfacere pardoseli	103.88	mp		
7	Montat parchet laminat 10 mm grosime, inclusiv montat plinta	103.88	mp		
8	Turnat sapa egalizare 5 cm grosime medie	1.12	mp		
9	Spituit pardoseli	2.24	mp		
10	Montat gresie	2.24	mp		
11	Montat pervaz interior PVC la ferestre	21.60	m		
12	Placare glafuri cu placi rigip lipite cu adeziv	18.96	mp		
13	Demontat + montat usi lemn	6.00	mp		
14	Montat jaluzele verticale	43.96	mp		
15	Montat praguri usi	3.00	buc		
16	Montare si demontare schela metalica	230.00	mp		
	TOTAL ORE NORMATE FINISAJE				
	TARIF SERVICE				
	TOTAL VALOARE ORE NORMATE FINISAJE				

NR. CRT	DENUMIREA LUCRARII	CANT	UM	ORE NORMATE / UM	TOTAL
	INSTALATII TERMICE				
1	Demontat registre incalzire existente	8.00	buc		
2	Montare convectoare tip panou din otel 600 x 1200 mm	8.00	buc		
3	Montat robinet dublu reglaj de colt	16.00	buc		
4	Montat robinet cu cep de inchidere	16.00	buc		
5	Montat robinet dublu reglaj de colt dn 20	11.00	buc		
6	Teava Cu pentru inst incalzire sudata Dn 25	103.00	m		
7	Proba de etansare la presiune in inst incalzire	11.00	mp		
8	Proba de dilatatie - contractie la inst incalzire	11.00	mp		
9	Proba de etanseitate la presiune la conducte cu Dn 25	83.00	m		
10	Proba de dilatatie - contractie la conducte cu Dn 25	83.00	m		
11	Montat bratari fixare teava din otel Dn 22	83.00	buc		
12	Montat bratari fixare teava din otel Dn 18	17.00	buc		
13	Strapungeri in pereri de beton	7.00	buc		
	TOTAL ORE NORMATE INST ALATII TERMICE				
	TARIF SERVICE				
	TOTAL VALOARE ORE NORMATE INSTALATII TERMICE				

NR. CRT	DENUMIREA LUCRARI	CANT	UM	ORE NORMATE / UM	TOTAL
	INSTALATII ELECTRICE				
1	Demontare aparate - prize, intrerupatoare, lampi	36.00	buc		
2	Demontat legaturi electrice aparate	106.00	buc		
3	Pozat copex in perete	27.00	m		
4	Pozare cablu MYF 2.5 mmp	54.00	m		
5	Executat cap terminal cablu	8.00	buc		
6	Pozare cablu MYF 1.5 mmp	42.00	m		
7	Montat prize	15.00	buc		
8	Montat intrerupator	8.00	buc		
9	Montat lampi iluminat 4x18W	14.00	buc		
10	Montat spoturi	17.00	buc		
	TOTAL ORE NORMATE INST.ELECTRICE				
	TARIF SERVICE				
	TOTAL VALOARE ORE NORMATE INSTALATII ELECTRICE				

B. MATERIALE SI PIESE DE SCHIMB

			APROVIZIONAT					
Denumire material			PLK			AG		
Material	UM		Cant	Pret unit	Valoare	Cant	Pret unit	Valoare
FINISAJE								
1 Glet	kg					552.86		
2 Amorsa	L					29.09		
3 Vopsea lavabila de interior alba	kg					87.20		
4 Coltar AL protectie muchii pereti si grinzi	m					152.00		
5 Tavan fals - placa 0,6x0,6	mp					88.40		
6 Tavan fals - profil principal 24 mm	m					70.89		
7 Tavan fals - profil secundar	m					141.44		
8 Tavan fals - profil de compartimentare	m					70.72		
9 Tavan fals - profil perimetral	m					44.20		
10 Tavan fals - diblu filetat	buc					88.40		
11 Tavan fals - tije filetata	buc					88.40		
12 Tavan fals - piesa de suspendare plafon	buc					88.40		
13 Tavan fals - saiba	buc					88.40		
14 Tavan fals - piulita	buc					176.80		
15 Tavan fals - surub cu diblu 6x42 mm	buc					293.49		
16 Parchet laminat 10 mm grosime	mp					109.60		
17 Folie polietilena pt suport parchet	mp					109.60		
18 Plinta PVC parchet, inclusiv coltare interioare/exterioare	m					113.20		
19 Ciment pt preparare sapa	kg					11.42		
20 Nisip pt preparare sapa	mc					0.06		
21 Gresie (inclusiv pt plinta)	mp					2.31		
22 Mortar adeziv pt gresie	kg					12.32		
23 Chit pt rosturi	kg					1.12		
24 Pervaz interior la ferestre - glaf tip helolit	m					21.60		
25 Placi rigips pt executie glafuri	mp					19.72		
26 Adeziv pt placare rigips	kg					104.28		
27 Usi lemn	mp					6.00		
28 Feronerie usi (broasca, butuc, sild, maner)	set					3.00		

29	Jaluzele	mp				43.96		
30	Praguri usi	m				3.00		
INSTALATII TERMICE								
1	Radiator otel 600/22/1400	buc				8.00		
2	Robinet tur 1/2"	buc				16.00		
3	Robinet retur 1/2"	buc				16.00		
4	Robinet cu cep de inchidere Dn 20	buc				11.00		
5	Teava cupru Dn 18	m				41.00		
6	Teava cupru Dn 22	m				62.00		
7	Bratari fixare Dn 22	m				65.00		
8	Bratari fixare Dn 18	m				17.00		
9	Niplu 18x 1/2"	buc				14.00		
10	Niplu 22x 3/4"	buc				14.00		
11	Cot Dn 18	buc				6.00		
12	Cot Dn 22	buc				9.00		
INSTALATII ELECTRICE								
1	TUB COPEX D=20	m				27.00		
2	MYF 2,5	m				54.00		
3	MYF 1,5	m				42.00		
4	PRIZE	buc				15.00		
5	INTRERUPATOARE	buc				8.00		
6	Corpuri de iluminat 4x18 W, inclusiv 4 tuburi fluorescente 18 W	buc				14.00		
7	SPOTURI	buc				17.00		
8	Ipsos modelaj	saci				0.70		
9	Bride pvc 250x3 albe	buc				34.00		
10	Panza flex 125X1.2	buc				0.00		
11	Izolatie PVC	buc				2.00		
TOTAL MATERIALE					0.00			
COTA APROVIZIONARE %								
TOTAL GENERAL MATERIALE					0.00			

C. UTILAJE

Denumire utilaj		Nr ore	Valoare	TOTAL
Autobasculanta pt evacuat deseuri	ore	8.00		
TOTAL UTILAJE	LEI			

TOTAL GENERAL A+B+C (fara mat. PLK)	LEI fara TVA	0.00
--	---------------------	-------------

ANTREPRENOR

BENEFICIAR

July 2

Sc. PETROTEL-LUKOIL S.A.
BIROU C.P.S.C.T.
SPECIALIST DEZIVE
TURUS CRISTIAN
10.10.2014