

ANTEMASURATOARE

INSTALATIA :

LUCRARE: AMENAJARI INTERIOARE PAVILION A PLK - PARTER, SPATIU MUZEU

A. MANOPERA NORMATIV

NR. CRT	DENUMIREA LUCRARII	CANT	UM	ORE NORMATE / UM	TOTAL
	STRUCTURA METALICA				
1	Confectie si montaj structura metalica	180.00			
	TOTAL ORE NORMATE STRUCTURA METALICA	ORE			
	TARIF SERVICE	LEI / ORA			
	TOTAL VALOARE ORE NORMATE STRUCTURA METALICA	LEI			

NR. CRT	DENUMIREA LUCRARII	CANT	UM	ORE NORMATE / UM	TOTAL
	FINISAJE				
1	Glet la pereti si tavane	327.50	mp		
2	Amorsa + zugraveli lavabile 2 straturi culoare alba	327.50	mp		
3	Montat coltare AL la pereti si grinzi	145.00	m		
4	Demontat tavan fals casetat	63.00	mp		
5	Desfacere pardoseli	60.76	mp		
6	Spituit pardoseli	60.76	mp		
7	Turnat sapa egalizare grosime medie 4 cm	60.76	mp		
8	Montat mocheta recuperata din PLK	60.76	mp		
9	Montat pervaz interior PVC la ferestre	19.80	m		
10	Zidarie caramida	0.90	mc		
11	Demolat manual zidarie, beton	5.74	mc		
12	Tencuieli driscuite grosime medie 2,5 cm	24.80	mp		
13	Montat usa dubla de sticla 1,5 x 2,05 m, cu mecanism inchidere tip Dorma	3.08	mp		
14	Montat jaluzele verticale	25.92	mp		
15	Montare si demontare schea metalica	230.00	mp		
	TOTAL ORE NORMATE FINISAJE	ORE			
	TARIF SERVICE	LEI / ORA			
	TOTAL VALOARE ORE NORMATE FINISAJE	LEI			

NR. CRT	DENUMIREA LUCRARII	CANT	UM	ORE NORMATE / UM	TOTAL
	INSTALATII TERMICE				
1	Demontat registre incalzire existente	8.00	buc		
2	Montare convectoare tip panou din otel 600 x 1200 mm	8.00	buc		
3	Montat robinet dublu reglaj de colt	16.00	buc		
4	Montat robinet cu cep de inchidere	16.00	buc		
5	Montat robinet dublu reglaj de colt dn 20	11.00	buc		
6	Teava Cu pentru inst incalzire sudata Dn 25	103.00	m		
7	Proba de etansare la presiune in inst incalzire	11.00	mp		

8	Proba de dilatatie - contractie la inst incalzire	11.00	mp		
9	Proba de etanseitate la presiune la conducte cu Dn 25	83.00	m		
10	Proba de dilatatie - contractie la conducte cu Dn 25	83.00	m		
11	Montat bratari fixare teava din otel Dn 22	83.00	buc		
12	Montat bratari fixare teava din otel Dn 18	17.00	buc		
13	Strapungeri in pereri de beton	7.00	buc		
	TOTAL ORE NORMATE INSTALATII TERMICE	ORE			
	TARIF SERVICE	LEI / ORA			
	TOTAL VALOARE ORE NORMATE INSTALATII TERMICE	LEI			

NR. CRT	DENUMIREA LUCRARI	CANT	UM	ORE NORMATE / UM	TOTAL
	INSTALATII ELECTRICE				
1	Demontare aparate - prize, intrerupatoare, lampi	36.00	buc		
2	Demontat legaturi electrice aparate	106.00	buc		
3	Pozat copex in perete	27.00	m		
4	Pozare cablu MYF 2.5 mmp	54.00	m		
5	Executat cap terminal cablu	8.00	buc		
6	Pozare cablu MYF 1.5 mmp	42.00	m		
7	Montat prize	15.00	buc		
8	Montat intrerupator	8.00	buc		
9	Montat lampi iluminat 4x18W	14.00	buc		
10	Montat spoturi	17.00	buc		
	TOTAL ORE NORMATE INSTALATII ELECTRICE	ORE			
	TARIF SERVICE	LEI / ORA			
	TOTAL VALOARE ORE NORMATE	LEI			

B. MATERIALE SI PIESE DE SCHIMB		APROVIZIONAT					
Denumire material		PLK			AG		
Material	UM	Cant	Pret unit	Valoare	Cant	Pret unit	Valoare
STRUCTURA METALICA							
1 Profile diverse structura metalica	kg				180.00		
FINISAJE							
1 Glet	kg				622.25		
2 Amorsa	L				32.75		
3 Vopsea lavabila de interior alba	kg				98.25		
4 Coltari AL protectie muchii pereti si grinzi	m				145.00		
5 Cement pt preparare sapa	kg				619.75		
6 Nisip pt preparare sapa	mc				3.40		
7 Pervaz interior la ferestre - glaf tip helolit	m				19.80		
8 Caramida	buc				380.00		
9 Cement pt preparare mortar zidarie	kg				22.32		
10 Nisip pt preparare mortar zidarie	mc				0.196		
11 Cement pt preparare mortar tencuieli	kg				224.44		
12 Nisip pt preparare mortar tencuieli	mc				0.79		
13 Var hidratat pt preparare mortar tencuieli	kg				15.80		
14 Usa dubla de sticla 1,5 x 2,05 m, cu mecanism inchidere tip Dorma	mp				3.08		
15 Jaluzele	mp				25.92		
16 Tamplarie Aluminiu	mp				2.35		

INSTALATII TERMICE					
1	Radiator otel 600/22/1400	buc			8.00
2	Robinet tur 1/2"	buc			16.00
3	Robinet retur 1/2"	buc			16.00
4	Robinet cu cep de inchidere Dn 20	buc			11.00
5	Teava cupru Dn 18	m			41.00
6	Teava cupru Dn 22	m			62.00
7	Bratari fixare Dn 22	m			65.00
8	Bratari fixare Dn 18	m			17.00
9	Niplu 18x 1/2"	buc			14.00
10	Niplu 22x 3/4"	buc			14.00
11	Cot Dn 18	buc			6.00
12	Cot Dn 22	buc			9.00
INSTALATII ELECTRICE					
1	TUB COPEX D=20	m			27.00
2	MYF 2,5	m			54.00
3	MYF 1,5	m			42.00
4	PRIZE	buc			15.00
5	INTRERUPATOARE	buc			8.00
6	Corpuri de iluminat 4x18 W, inclusiv 4 tuburi fluorescente 18 W	buc			14.00
7	SPOTURI	buc			17.00
8	Ipsos modelaj	saci			0.70
9	Bride pvc 250x3 albe	buc			34.00
10	Panza flex 125X1.2	buc			0.00
11	Izolatie PVC	buc			2.00
TOTAL MATERIALE				0.00	
COTA APROVIZIONARE %					
TOTAL GENERAL MATERIALE				0.00	

C. UTILAJE

Denumire utilaj		Nr ore	Valoare	TOTAL
Autobasculanta pt evacuat deseuri	ore	8.00		
TOTAL UTILAJE	LEI			

TOTAL GENERAL A+B+C (fara mat. PLK)	LEI fara TVA	
--	---------------------	--

ANTREPRENOR

BENEFICIAR

Lucy

Lucy
S.C. PETROTEL-LUKOIL S.A.
BIROU C.P.S.C.T.
SPECIALIST DEVIZE
TURUS CRISTIAN