

CENTRALIZATOR VALORIC

**“Reabilitarea estacadei de conducte din zona cladirii compresoare aer
PADAAG”**

NR. CRT.	DENUMIRE LUCRARE	COD DEVIZ	VALOARE FARA TVA (LEI)
o1	o2	o3	o4
1	Reabilitarea estacadei de conducte din zona cladirii compresoare aer PADAAG	VOPS58	
TOTAL GENERAL (LEI) FARA TVA			

PETROLUL LUKOIL S.A.
BIROU C.P.S.C.T.
SPECIALIST DEVIZE
DIMITRESCU CORNELIA

[Signature] 01.07.2020

A N T E M A S U R A T O A R E

Deviz VOPS58 REABILITAREA ESTACADEI DE
CONDUCTE DIN ZONA CLADIRII
COMPRESOARE AER PADAAG

=====

Nr.	Simbol articol	UM	CANTITATEA
-----	----------------	----	------------

crt.

=====

001	IZD02A1	TONA	84.000
CURATIRE RUGINA CU PERIE SIRMA A PIESELOR METALICE GRINZI ZABRELE, FERME, CONTRAVINTUIRI			

002	IZD03D1	TONA	84.000
VOPSIRE CU VOPS MINIU CU APARAT AER COMPR 1 STR PECONF SI CTII METAL EXEC DIN PROF GROS 8-12 MM			

003	IZD06B1	TONA	84.000
VOPSIRE 2 STRATURI CU VOPSEA ULEI LA CONSTRUCTII METALICE			

003	6106117	KG	-420.000
EMAIL ALB E.101-8 NTR 90-73			

003	6103218	KG	420.000
VOPSEA ULEI ORICE CULOARE			

004	CB47A1	MP.	980.000
MONTAREA SI DEMONTARE SCHELEI MET TUBULARE PT LUCRARI PE SUPRAFETE VERTICALE H<30,0M			

005	CL17B1	[1]TONA	9.000
DEMONTAREA CONSTRUCTIILOR METALICE FARA RECUPERAREA SUBANSAMBLELOR REFOLOSIBILE			

006	TRB05A25	TONA	29.580
TRANSPORTUL MATERIALELOR PRIN PURTAT DIRECT.MATERIALE INCOMODE SUB 25 KG DISTANTA 50M			

007	TR11AA01F1	TONA	29.580
INCARCAREA MATERIALELOR, GRUPA A-GRELE SI MARUNTE, PRIN TRAN.PINA LA 10M RAMPA SAU TEREN-AUTO CATE			

008	TRA02A02	TONA	29.580
TRANSPORTUL RUTIER AL MATERIALELOR, SEMIFABRICATELOR CU AUTOCAMIONUL PE DIST.= 2 KM.			

009	TR11AA08F1	TONA	29.580
DESCARCAREA MATERIALELOR, GRUPA A-GRELE SI MARUNTE PRIN TRANS.PINA LA 10M AUTO- RAMPA, TEREN CATEG.			

010	AUT6729	ORA	4.000
MACARA PE PNEURI 10-14,9TF			

011 CA02C1 M.C. 25.000
TURNARE BETON ARMAT IN FUNDATII
CONTINUE, RADIARE SI PERETI SUB COTA ZERO
A CONSTR CU GROS <30CM

011 2100995 M.C. 25.200
BETON DE CIMENT B 400 STAS 3622

012 TRA06A10 TONA 66.250
TRANSPORTUL RUTIER AL BETONULUI-
MORTARULUI CU AUTOBETONIERA DE 5,5MC
DIST. =10KM

Intocmit,

Verificat,

[Handwritten signature]



[Handwritten signature]
01.07.2020